

SERIES AT A GLANCE

TELESCOPIC ARTICULATED

DLT2 SERIES

- Working height up to 67'
- Material handling or 2-person basket options
- Top-mounted jib lifts up to 1000#, optional
- Basket elevator option; 180-degree basket rotator
- Fiberglass or aluminum basket options
- Insulated, Cat. C & D (DLT2); non-insulated (DLT2S)



DPM3 SERIES

- Working height up to 60'8"
- 36" X 60" bottom-mount, aluminum basket
- Auxiliary winch lifts up to 150#, optional
- 180-degree basket rotator
- Insulated, Cat. D (DPM3) or non-insulated (DPM3S)



DPM2 SERIES

- Working height up to 59'
- Material handling or 2-person basket options
- Top-mounted jib lifts up to 1000#, optional
- Basket elevator option; 180-degree basket rotator
- Fiberglass or aluminum basket options
- Insulated, Cat. C & D (DPM2); non-insulated (DPM2S)



DPM SERIES

- Working height up to 57'
- Material handling or 2-person basket options
- Side-mounted jib lifts up to 1000#, optional
- 180-degree basket rotator; 3 basket styles
- Fiberglass or aluminum basket options
- Insulated, cat. C & D (DPM); non-insulated (DPMS)



DTAX2 SERIES

- Working height up to 49'
- Up to 400# basket capacity
- 180-degree basket rotator
- Fiberglass or aluminum basket options, 24"x24"
- Options available for use with 9' body
- Insulated, Cat. C & D (DTAX2) or non-insulated (DTAX2S)



DTA2 SERIES

- Working height up to 45'
- Up to 400# basket capacity
- Fiberglass or aluminum basket options, 24"x24"
- Options available for use with 9' body
- Insulated, Cat. D (DTA2) or non-insulated (DTA2S)

TELESCOPIC

DPM2-32

- Telescopic DPM2
- Working height up to 39'

DPM-32

- Telescopic DPM
- Working height up to 37'

DTX2 SERIES

- Telescopic DTAX2
- Working height up to 39'

DT2 SERIES

- Telescopic DTA2
- Working height up to 36'

BUCKET VAN



DVS BUCKET VAN

Telescopic aerial mounted on a cutaway chassis

DVT BUCKET VAN

Telescopic aerial mounted on a transit cargo van

ARTICULATED



DO SERIES

Overcenter; working height up to 41'; side reach to 30'4"

DSL SERIES

Non-overcenter; working height up to 38'; side reach to 19'10"

SPECIALTY



DCP CABLE PLACER

Telescopic articulated cable placer; 400# side pull; 50# down pull

URBAN FORESTRY PACKAGE

Telescopic articulating bucket truck with aluminum chipper box

